



Weight: 14,200 lbs
 Heaviest Lift: 7,100 lbs



Standard Features

- 4500 PSI Concrete @ 28 Days
- Design for Aircraft Loading
- Galvanized Pulling Irons
- 12" Dia. Sump
- 1/2" Dia. Threaded Inserts
- Manufactured in NPCA Certified Plant

Standard Options

- Cast Iron Frame and Cover
- Cover Lettering Option Available
- 6" & 12" Precast Adjustment Rings
- 4" & 6" Dia. Duct Terminators



T: 269-342-0539
 F: 269-344-4810
 qualityprecastinc.com

7800 ADOBE RD.
 KALAMAZOO, MI